



**KERALA LIVESTOCK
DEVELOPMENT BOARD Ltd.**

(A Government of Kerala undertaking)

An ISO 9001 : 2008 Certified Company

CE/155/2013 (A)/Vol.II

2799

Dated: 09.10.2018

SHORT RE- QUOTATION NOTICE

Competitive quotations are invited for the operation and maintenance of the Electrical Installations at the Genomic Laboratory of the KLD Board at Kudappanakkunnu from:

a) Electrical Contractors with "A" Class Licence

OR

b) A team of individuals comprising of one Electrical Supervisor possessing an "A" Grade Supervisor Licence and Wiremen possessing valid Electrical Wiremen Licence.

SCOPE OF WORK:

To be the Designated Contractor/ Person under Regulation 3 of Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations, 2010 for the operation and maintenance of Electrical Equipments installed at Genomic Laboratory, Kerala Livestock Development Board Ltd., Kudappanakkunnu, Thiruvananthapuram of Kerala Livestock Development Board Ltd.

QUALIFICATION:-

The Bidder should be:

a) An Electrical Contractor having a valid "A" Class Licence issued by the Kerala State Electricity Licencing Board and fulfilling the required scope of permit as per norms of the Department of Electrical Inspectorate, Government of Kerala to operate and maintain the electrical installation at the site as detailed below

OR

b) A team of individuals comprising of one Electrical Supervisor possessing Degree/ Diploma in Electrical Engineering and possessing an "A" Grade Supervisor Licence issued by the Kerala State Electricity Licencing Board and Wiremen possessing valid Electrical Wiremen Licence issued by the Kerala State Electricity Licencing Board. The team shall be fulfilling the required scope of permit as per norms of the Department of Electrical Inspectorate, Government of Kerala to operate and maintain the electrical installation at the site as detailed below

The installation avails electric supply from KSEB Ltd. at 11 kV and is having the following connected equipments.

Sl. No	Equipment	Make	Quantity
1	HT Load Break Switch	Unipower GS Switchgear	1 Number
2	Transformer 11kV/433V,160kVA	Unipower Transformers Pvt. Ltd.	1 Number
3	DG Set 125kVA	Alternator: Stamford, Engine: Cummins	1 Number
4	GCP Breaker 200A MCCB		1 Number
5	Capacitors (Total)		40kVAR
6	UPS		60kVA
7	Total Connected Load		42.6kW

Offers along with the full particulars of the Contractors/Individuals, details regarding works of similar nature carried out during the last three years etc. must reach the Office of the undersigned on or before **25.10.2018 at 3.00 pm** through *Regd. Post/Speed Post only*. Further details can be had from this office on all working days. Offers received through any other means (Courier, by hand etc.) will not be considered.

Sd/-
Managing Director

Copy to:- 1) All Unit Heads
2) Computer Assistant for networking
3) Notice Board at H. O

//Approved for issue//


Assistant Engineer